

LONG LAKE PARK ELECTRICAL WORK

BID SPECS:

- A. Existing 200 amp panel #1
Disconnect circuit 5/7
Disconnect circuit 6/8

OPTIONAL UPGRADES:

- 1) Add 2 new pedestals and additional underground wiring to adequately supply 5 total pedestals
- 2) Add 2 new pedestals and upgrade all 5 pedestals to 50/30/20 with adequate underground wiring

- B. Existing 200 amp panel #2
Disconnect circuit 5/7
Disconnect circuit 6/8
Add additional pedestal to provide power to sites 43, 44 & 72. See picture
Connect pedestal at sites 41/74 and run underground wiring to adequately supply sites

OPTIONAL UPGRADES:

- 1) Change pedestals and wiring to upgrade to 50/30/20 pedestals

- C. Existing panel #3
Disconnect circuit #25/27

- D. Install new 200 amp panel #4 near camp sites #7/8 and connect wiring for separate circuits supplying sites 1 to 6 and sites 7 to 12

- E. Install new 200 amp panel #5 and supply power to campsites 48 to 53 and 66/67

OPTIONAL UPGRADES:

- 1) Install additional pedestals and wiring at sites 53/66 and 54/65
- 2) Upgrade 5 pedestals to 50/30/20

- F. Install new 200 amp panel #6 and underground wiring to adequately supply campsites 13 to 22

OPTIONAL UPGRADES:

- 1) Upgrade pedestals and wiring to supply 50/30/20

- G. Install new 200 amp panel #7 and supply underground wiring to supply campsites 35 to 40 and 75 to 80

OPTIONAL UPGRADES:

- 1) Add additional pedestals to supply power to sites 36/79 and 38/77
- 2) Upgrade all pedestals and wiring to supply sites 35 to 40 and 75 to 80 with 50/30/20 pedestals

- H. Install new 200 amp panel #8 and two circuits to supply sites 29 to 34 and sites 23 to 28

OPTIONAL UPGRADES:

- 1) Upgrade all wiring and pedestals to 50/30/20

- I. Install new 200 amp panel on gable end of South bath house
Install 4 GFCI 20 amp weather proof outlets on side of bath house
Supply 100 amp feed to existing panel

OPTIONAL UPGRADES:

- 1) Install a 50 amp sub panel at each pavilion with 3 circuits providing power to GFCI weatherproof outlets

- J. All wiring must meet current electrical code

- K. All work to be done by licensed and insured contractor

- L. All permits to be the responsibility of the contractor

- M. Any pedestals or wiring removed is to remain property of Alpena County

- N. All work to be completed prior to December 31, 2018

- O. Prebid walk through September 18th at 4:00 p.m. at Long Lake Park

- P. Bid deadline is 9:00 a.m. October 2nd

- Q. Bids submitted to Alpena County Commissioners Office, 720 W. Chisholm St., Suite #7, Alpena, MI 49707 or email to bids@alpenacounty.org

Rates

Waterfront - \$31.00
 Regular w/E \$26.00
 Rustic - \$21.00

LONG LAKE CAMPGROUND

10002 Hinks Park Rd. Alpena, MI 49707

Phone: 989-595-2401

Boat Launch

Daily \$5.00
 Seasonal \$30.00

